


CONDUIT ENCASEMENT

FULL WIDTH OF ROADWAY CURB TO CURB

NOTES:

1. DETECTABLE MULE TAPE SHALL BE INSTALLED IN ALL CONDUIT RUNS.
2. ALL EMPTY CONDUIT ENDS SHALL BE PLUGGED WITH CONDUIT PLUGS.
3. ALL CONDUIT SHALL BE SCHEDULE 40 PVC OR HDPE.
4. THIS DETAIL SHALL BE USED FOR TRAFFIC SIGNAL CONDUIT STREET CROSSINGS
5. IF CONDUIT IS UNDER NATIVE SOIL, 1/2 SACK SLURRY ENCASEMENT IS ACCEPTABLE.
6. NEW PAVEMENT CUTS AND NEW PAVEMENT MUST CONFORM TO THE CITY OF GLENDALE ENGINEERING STANDARDS AND MAG STANDARD SPECIFICATIONS, SECTION 336.

<p>APPROVED BY _____ DATE _____</p>	 GLENDALE	<p>CITY OF GLENDALE TRAFFIC SIGNAL AND ITS STANDARDS</p>	<p>REVISION: 7/2009</p>
<p>TYPICAL SIGNAL CONDUIT DETAILS</p>			<p>T2-12</p>